# STEELWAVE

# INDUSTRIAL PARK

2,580 INDUSTRIAL BLVD HAYWARD, CA

## DEVELOPER

STEELWAVE STEELWAVE, LLC 2050 MAIN STREET, SUITE 830

MICHAEL OLSON PH: (925) 980-9595

GENERAL CONTRACTOR

TBD

## OWNER'S CONSULTANTS

CIVIL ENGINEER/LAND SURVEYOR

WARE MALCOMB 4683 CHABOT DRIVE SUITE 300 PLEASANTON, CA 94588

PH: (925) 244-9620 FAX: (925) 244-9621

STEVE TSANG

GEOTECHNICAL ENGINEER

BERLOGAR GEOTECHNICAL CONSULTANTS 5587 SUNOL BOULEVARD

PLEASANTON, CA 94566

PH: (925) 484-0220 FAX: (925) 846-9645

### ARCHITECT

### WARE MALCOMB

4683 CHABOT DRIVE, SUITE 300

PH: (925) 244-9620 FAX: (925) 244-9621

# EXTERIOR CONCEPTUAL IMAGE



SHEET INDEX

WARE Leading Design

(TOTAL SHEETS = 17 )

A0.1 TITLE SHEET
A1.0 SITE PLAN
A2.1 FLOOR PLAN EXTERIOR ELEVATIONS

ARCHITECTURAL

PRELIMINARY GRADING PLAN

PRELIMINARY UTILITY PLAN PRELIMINARY STORMWATER MANAGMENT PLAN FIRE SUPRESSION EXHIBIT

PEDESTRIAN AND VEHICULAR CIRCULATION PLAN
SEMI-TRUCK AND REFUSE COLLECTION TRUCK TURNING EXHIBIT

LANDSCAPE

LANDSCAPE PLAN IRRIGATION PLAN



LANDSCAPE ARCHITECT

960 ATLANTIC AVENUE ALAMEDA, CA 94501

JIM BENSMAN PH: (510) 353—3954

Pound or Number Architectural Bituminous BLDG. BLK. Block BLKG. Blocking

Caulking

Concrete

Connection

Cased Opening

Center of Mullion

B.O.M.

B.O.P.

CONC.

CONN.

Drinking Fountain Downspout Dry Standpipe Each Expansion Joint Elevation Bottom of Concrete Electrical Bottom of Mullion Elevator Bottom of Panel Emergency Bottom of Reveal Enclosure Electrical Panelboard Equal EQPT. Equipment Electric Water Cooler Cement EXST. Ceramic EXPO. Cast Iron Exposed Expansion Corner Guard Exterior

Fluorescent Face of Finish FTG. MUL. FURR. Furring Future GALV. Galvanized G.B. Grab Bar N.T.S. Ground Grade OBS. Gypsum 0.C. 0.D. 0FF. Hollow Core Hardwood OPNG. HDWE. Hardware Hollow Metal HORIZ. Horizontal Hour HGT. Height

Interior

Kitchen

Knock Out

Joint

K.O.

**ABBREVIATIONS** 

LAB. LAM. LAV. LKR. LT.

Mechanical

Mullion

Number

Nominal

Obscure

Office

On Center

Reference REFR. Refrigerator RGTR. Register Reinforced Not In Contract REQ. RESIL. Required Resilient RM. Room Not To Scale R.O. Rough Opening RWD. Redwood R.W.L. Rain Water Leader Self Adhered Flashing Outside Diameter (Dim.) Solid Core Seat Cover Dispenser SCHED.

STA.

Station

T.P. T.P.D. T.V. T.W. TYP. UNF. U.O.N. UR. VERT. Schedule Soap Dispenser W.C. W/O Shower Sheet Sanitary Napkin Disp. S.N.R. Sanitary Napkin Recept. WT. Specification Stainless Steel Service Sink

BUILDING DEPARTMENT:

STA. STD. STL.

T.O.M.

T.O.W.

Top of Curb Top of Reveal Top of Mullion Top of Wall Top of Pavement Toilet Paper Dispenser Television Top of Wall Unfinished

Unless Otherwise Noted Urinal Vertical Vestibule West With Water Closet Without Waterproofing Membrane Wheather/Water Resistive Barrier Wainscot

**BUILDING CODES:** 2013 CALIFORNIA BUILDING CODE 2013 CALIFORNIA BUILDING CODE 2013 CALIFORNIA MECHANICAL CODE 2013 CALIFORNIA ELECTRICAL CODE 2013 CALIFORNIA PLUMBING CODE 2013 CALIFORNIA FIRE CODE (WITH LOCAL 2013 STATE OF CALIFORNIA ENERGY CODE 2013 STATE OF CALIFORNIA GREEN 2013 STATE OF CALIFORNIA TITLE 24 ASSESSOR'S PARCEL NO.: ZONING CLASSIFICATION:  $\_$ BP (BUSINESS PARK) OCCUPANCY CLASSIFICATION: \_\_\_\_\_ SECTION 306 - S1/B TYPE OF CONSTRUCTION:  $\_$ \_ PER CBC CHAPTER 6 (SECTION 602) - IIIB SPRINKLERED: NUMBER OF STORIES: \_ PROJECT SCOPE: CONSTRUCTION OF SINGLE STORY COLD DARK SHELL SPEC BUILDING WITH SITE IMPROVEMENTS. FLOOD ZONE: THE SUBJECT PROPERTY IS SHOWN ON THE FEDERAL EMERGENCY MANAGEMENT AGENCY FLOOD INSURANCE RATE MAP, COMMUNITY PANEL NUMBER 065033 0427 G DATED AUGUST 03, 2009, AS BEING LOCATED IN FLOOD ZONE "X".

AREAS OF 0.2% ANNUAL CHANCE FLOOD; AREAS OF

LESS THAN 1 FOOT OR WITH DRAINAGE AREAS LESS

THAN 1 SQUARE MILE; AND AREAS OF PROTECTED

LEVEES FROM 1% ANNUAL CHANCE FLOOD.


(WWW.FEMA.GOV) ON JUNE 22, 2016.

1% ANNUAL CHANCE FLOOD WITH AVERAGE DEPTHS OF

INFORMATION WAS OBTAINED FROM THE FEMA WEBSITE

PROJECT DATA

PROJECT SITE




NO SCALE

# DEFERRED SUBMITTALS


1- CEQA DOCUMENTATION AND SUBMITTAL

SNR16-0049-0 JOB NO.:



WARE Leading Design

DRAWN BY: LDB JOB NO.: SNR16-0049-00



NOL










AERIAL CONTEXT VIEW (10 YEAR OUTLOOK)
SCALE: NTS



ENTRANCE CLOSE-UP

SCALE: NTS

SOUTH ENTRANCE PERSPECTIVE
SCALE: NTS



#### PERVIOUS AND IMPERVIOUS SURFACES COMPARISON TABLE Project Phase Number: Total Site (acres): Total Area of Site Disturbed (acres): Proposed Condition of Site Area Disturbed **Existing Condition of** Site Area Disturbed (square feet) Replaced Impervious Surfaces 93,350 76,650 12,800 Sidewalks, Patios, Paths, etc 4,000 4,000 Streets (Public) Streets (Private) 182,800 Total Impervious Surfaces 4,000 4,000 Pervious Surfaces 239,800 57,000 Landscaped Areas Pervious Paving Other Pervious Surfaces (green roof, etc.) Total Pervious Surfaces: 186,800 Total Proposed Replaced + New Impervious Surfaces: Total Proposed Replaced + New Pervious Surfaces: 57,000

DRAINAGE	PERVIOUS AREA	IMPERVIOUS AREA		REQUIRED BIO	PROVIDED BIO
MANAGEMENT AREAS	(Sq.Ft.)	(Sq.Ft.)	TOTAL (Sq.Ft.)	TREATMENT (Sq.Ft.)	TREATMENT (Sq.Ft.)
1	17,000	32,800	49,800	1,312	2,400
2	18,080	47,420	65,500	1,897	1,900
3	18,400	82,200	100,600	3,288	3,341
4	3,520	24,380	27,900	975	975
Total	57,000	186,800	243,800	7,472	8,616

#### BIO-TREATMENT BASIN MAINTENANCE PLAN

1 OBJECTIVES: THE MAINTENANCE OBJECTIVES FOR BIO-TREATMENT BASIN SYSTEMS INCLUDE KEEPING UP THE

HYDRAULIC AND REMOVAL EFFICIENCY OF THE BASIN AND MAINTAINING A DENSE, HEALTHY GRASS (OR PLANT)
COVER.

2 INSPECTION SCHEDULE
2.1 VISUAL INSPECTIONS SHALL BE CONDUCTED MONTHLY, PARTICULARLY AFTER HEAVY RUNOFF, TO ENSURE NORMAL FUNCTIONING OF BIO—TREATMENT BASIN.

2.2 DETAILED INSPECTIONS SHALL BE CONDUCTED AT LEAST TWICE ANNUALLY WITH INSPECTIONS OCCURRING (1) AT THE END OF THE WET SEASON TO SCHEDULE SUMMER MAINTENANCE, (2) BEFORE MAJOR FALL RUNOFF IN PREPARATION FOR WINTER, AND (3) AFTER PERIODS OF HEAVY RUNOFF.
THE OBJECTIVE OF DETAILED INSPECTIONS IS TO IDENTIFY EROSION, DAMAGE TO VEGETATION, GRASS OR PLANT
HEIGHT, DEBRIS, LITTER, AREAS OF SEDIMENT ACCUMULATION, AND POOLS/STANDING WATER. IF ANY ISSUES
EXIST, ACTIVITIES AS OUTLINED IN SECTION 3, MAINTENANCE ACTIVITIES WILL BE CONDUCTED.

3.1 ROUTINE OR PREVENTATIVE MAINTENANCE REFERS TO PROCEDURES THAT ARE PERFORMED ON A REGULAR BASIS
TO KEEP THE BIO-TREATMENT BASIN AESTHETIC AND IN PROPER WORKING ORDER. ROUTINE MAINTENANCE
INCLUDES DEBRIS REMOVAL, SILT AND SEDIMENT REMOVAL, AND CLEARING OF VEGETATION AROUND FLOW CONTROL DEVICES TO PREVENT CLOGGING. ROUTINE MAINTENANCE ALSO INCLUDES THE MAINTENANCE OF A HEALTHY VEGETATIVE COVER. DEAD TURF OR OTHER UNHEALTHY VEGETATIVE AREAS WILL NEED TO BE REPLACED AFTER BEING DISCOVERED.

3.1.1 EROSION: AREAS OF EROSION AND SLOPE FAILURE SHALL BE REPAIRED AND REPLANTED AS SOON AS POSSIBLE. ERODED AREAS NEAR THE INLET OR OUTLET MAY ALSO NEED TO BE LINED WITH RIPRAP, WHICH WILL BE DETERMINED ON A CASE BY CASE BASIS.

3.1.2DAMAGE TO VEGETATION: IF THE BASIN DEVELOPS RUTS OR HOLES, IT SHALL BE REPAIRED UTILIZING A SUITABLE SOIL THAT IS PROPERLY TAMPED AND SEEDED. THE GRASS OR PLANT COVER SHOULD BE THICK; IF IT IS NOT, IT SHALL BE REPLANTED WITH IN-KIND PLANTS, AS NECESSARY. IF POSSIBLE, FLOW WILL BE REDIRECTED UNTIL NEW PLANTINGS ARE FIRMLY ESTABLISHED TO AVOID DETERIORATION. IF INVASIVE SPECIES AND/OR WEEDS DEVELOP, PROMPTLY REMOVE TO AVOID DISRUPTION TO ORIGINAL VEGETATION.

3.1.3GRASS OR PLANT HEIGHT: MOW OR PRUNE AS REQUIRED BY PLANT VARIETY TO MAINTAIN AT LEAST A 4-6" GRASS HEIGHT, DENSE PLANT GROWTH AND/OR TO SUPPRESS WEEDS AND WOODY VEGETATION. LITTER MUST BE REMOVED PRIOR TO MOWING. MAINTAIN AS INDICATED BY SPECIES TO PROMOTE GROWTH AND POLLUTANT UPTAKE. REMOVE CUTTINGS AND DISPOSE /COMPOST.

3.1.4DEBRIS / LITTER: REMOVE ALL LITTER OR DEBRIS WITHIN BIO-TREATMENT BASIN AND PRIOR TO MOWING AND AS INSPECTIONS WARRANT. KEEP BIO-TREATMENT BASIN FREE OF DEBRIS.

3.1.5 AREAS OF SEDIMENT ACCUMULATION: REMOVE SEDIMENT BY HAND WITH A FLAT—BOTTOMED SHOVEL WHENEVER SEDIMENT COVERS VEGETATION OR BEGINS TO REDUCE BIO—TREATMENT BASIN CAPACITY. IF APPLICABLE MAINTAIN CLEAN CURB CUTS TO AVOID SOIL AND VEGETATION BUILDUP. SEDIMENT ACCUMULATING NEAR CULVERTS AND IN BASINS SHOULD BE REMOVED WHEN IT BUILDS UP TO 75 MM (3 IN.) AT ANY SPOT, OR COVERS VEGETATION. REMOVE ANY DEBRIS IN UNDER DRAINS THAT COULD CAUSE CLOGGING.

3.1.6 POOLS AND STANDING WATER: OBSERVE SOIL AT THE BOTTOM OF THE BIO—TREATMENT BASIN FOR UNIFORM PERCOLATION THROUGHOUT. IF PORTIONS OF THE BIO—TREATMENT BASIN DO NOT DRAIN WITHIN 5 DAYS AFTER THE END OF A STORM, THE SOIL SHALL BE TILLED AND REPLANTED WITH PLANTS SIMILAR TO THOSE ORIGINALLY PLANTED IN THE BIO—TREATMENT BASIN. REMOVE ANY DEBRIS OR ACCUMULATION OF SEDIMENT.

3.1.7IRRIGATION: WATER PLANTS IN BIO-TREATMENT BASINS DURING DRY CONDITIONS. CONFIRM THAT IRRIGATION IS ADEQUATE AND NOT EXCESSIVE.


3.1.8 PESTICIDES AND FERTILIZERS: APPLICATION OF PESTICIDES AND FERTILIZERS SHALL BE MINIMAL. BIOLOGICAL, PHYSICAL, AND CULTURAL CONTROLS SHALL BE USED PRIOR TO PESTICIDE AND FERTILIZER USE. 3.2<u>NON-ROUTINE OR CORRECTIVE MAINTENANCE</u> REFERS TO ANY REHABILITATIVE ACTIVITY THAT IS NOT PERFORMED ON A REGULAR BASIS. THIS INCLUDES FLOW CONTROL STRUCTURE REPLACEMENT OR THE MAJOR REPLACEMENT AND CLEANING OF AQUATIC VEGETATION. NON-ROUTINE MAINTENANCE WILL BE COMPLETED AS NEEDED. 4 VECTOR CONTROL


4.1 OBJECTIVE: TO PREVENT CONDITIONS WITHIN BIO-TREATMENT BASINS THAT ATTRACT AND/OR PROMOTE THE GROWTH OF DISEASE VECTORS, INCLUDING BUT NOT LIMITED TO MOSQUITOES, RODENTS, AND FLIES. 4.2 MAINTENANCE ACTIVITIES FOR VECTOR CONTROL

4.2.1INSPECTIONS: REGULAR INSPECTIONS WILL DETERMINE IF BIO—TREATMENT BASINS HAVE POOLS OF STANDING WATER OR DEBRIS ACCUMULATION. INSPECTIONS WILL BE CONDUCTED PRIOR TO THE RAINY SEASON, AFTER MAJOR STORM EVENTS, AND AT LEAST ONCE DURING THE DRY SEASON TO ASCERTAIN THAT STANDING WATER DRAINS FROM THE BIO—TREATMENT BASIN WITHIN 5 DAYS.

4.2.2 HOLES IN GROUND: ABATE POTENTIAL VECTORS BY FILLING HOLES IN THE GROUND IN AND AROUND THE BIO-TREATMENT BASIN AND BY INSURING THAT THERE ARE NO AREAS WHERE WATER STANDS LONGER THAN

4.2.3 OTHER MAINTENANCE ACTIVITIES: IF ANY OBSTRUCTIONS DEVELOP (E.G. DEBRIS ACCUMULATION, INVASIVE VEGETATION, CLOGGING OF OUTLETS AND/OR UNDER DRAINS) WITHIN THE BIO-TREATMENT BASIN, APPROPRIATE MAINTENANCE ACTIVITIES SHALL BE IMPLEMENTED TO CORRECT THE OBSTRUCTION.






- 1. BIORETENTION BASINS SHALL BE CONSTRUCTED UNDER THE OBSERVATION OF THE SOILS ENGINEER.
- 2. BIO-TREATMENT SOIL MIX (BSM) PER ATTACHMENT L OF THE C3 STORMWATER TECHNICAL GUIDELINE DATED APRIL 11TH 2016. WITH A MINIMUM INFILTRATION RATE OF 5" PER HOUR.
- 3. NO MULCH CAPABLE OF FLOATING SHALL BE PLACED IN THE BIORETENTION AREA
- 4. SEE "PLAN" FOR LAYOUT OF BIORETENTION BASIN AND PERF PIPE(S) ALIGNMENT

**BIORETENTION AREA** 

MB I Estate

DRAWN BY: JOB NO.: SNR15-0076-0



SEMI-TRUCK TURNING DIAGRAM SCALE: 1" = 40' REFUSE COLLECTION TRUCK TURNING DIAGRAM SCALE: 1" = 40'

